


NOTES:

1. BOARDWALK FRAME TO BE PRESSURE TREATED LUMBER. DECK BOARD TO BE COMPOSITE BOARD.
2. SIDEWALK SECTION AT EACH END OF BOARDWALK TO BE ADJUSTED TO ALLOW BOARDWALK DECK TO BE FLUSH WITH WALK. SIDEWALK TO MAINTAIN MIN. THICKNESS OF 4".
3. BOARDWALK TO BE CONSTRUCTED TO CURRENT ADA SPECIFICATIONS.
4. RAIL TO BE CONSTRUCTED AS SPECIFIED IN CITY OF BROOKHAVEN RAMP AND HANDICAP RAIL DETAILS.
5. HANDRAILS TO BE CONSTRUCTED ON BOARDWALKS 18" OR HIGHER.
6. HANDICAP RAILS TO BE INSTALLED ON ALL RAMPED PORTIONS OF BOARDWALK AS PER ADA REQUIREMENTS.
7. BOARDWALKS TO BE CONSTRUCTED ADJACENT TO SPECIMEN TREES WHERE A STANDARD SIDEWALK WOULD IMPACT CRITICAL ROOT ZONE. STANDARD SIDEWALK TO BE UTILIZED OUTSIDE CRITICAL ROOT ZONE.



NOT TO SCALE



CITY OF BROOKHAVEN
PUBLIC WORKS DEPARTMENT
BOARDWALK DETAIL