



ADDENDUM #1 ITB 18-151

Stratfield Drive Drainage Improvements Project - Phase 1

1. Can the structure be bricked, as long as the brick is DOT certified?
 - a. **All structures will be precast as indicated in the Storm Details sheet of the construction drawings.**
2. Will the replaced curb be put back as roll back curb?
 - a. **The curb which will be removed for Phase 1 will be replaced in kind, therefore existing rollback curb will be replaced with rollback curb, existing granite curb will be replaced with granite curb.**
3. Are throats and tops to be completed at the existing elevation?
 - a. **Yes.**
4. Will the driveways be replaced where the pipe crosses, or will the entire driveway be replaced?
 - a. **Two driveways (1503 and 1511 Ragley Hall Drive) will be replaced beginning at the disturbed trench for pipe replacement and continuing to the edge of pavement. This will include the gutter.**
5. What are the sizes of the trees to be planted?
 - a. **Refer to Sheet C4.00 for replacement tree details and notes.**
6. What season do you anticipate the planting to take place?
 - b. **Expect planting to occur near the end of the project – anticipate late summer – early fall.**
7. What are the sizes of the trees to be planted?
 - a. **Refer to Sheet C4.00 for replacement tree details and notes.**
8. What season do you anticipate the planting to take place?
 - a. **Expect planting to occur near the end of the project – anticipate late summer – early fall.**