



DATE: November 19, 2019

TO: All Bidders

FROM: City of Brookhaven Purchasing Department

RE: ITB No. 19-403, Briarwood Sidewalk Project

Please see Addendum No. 2 for the above-referenced solicitation.

ADDENDUM NO. 2
ITB NO. 19-403
BRIARWOOD SIDEWALK PROJECT

B. The following change has been made to the above referenced solicitation.

Delete: Pages 66, 64, 65 Bid Schedule

Add: Revised 11/19/2019 Pages 63-65 Bid Schedule

**EXHIBIT I
 BID SCHEDULE
 ITB 19-403, BRIARWOOB SIDEWALK PROJECT**

Item No.	Description	Units	Estimated Quantity	Unit Price	Total Price
	ROADWAY				
150-1000	TRAFFIC CONTROL - WALK 16-110	LS	1		
210-0100	GRADING COMPLETE - WALK 16-110	LS	1		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	100		
318-3000	AGGR SURF CRS	TN	100		
402-3103	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	60		
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	36		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	18		
413-0750	BITUM TACK COAT	GL	12		
441-0014	DRIVEWAY CONCRETE, 4 IN TK	SY	80		
432-0206	MILL ASPH CONC PVMT, 1 1/2 IN DEPTH	SF	4900		
441-0104	CONC SIDEWALK, 4 IN	SY	820		
441-0108	CONC SIDEWALK, 8 IN	SY	63		
441-0300	CONC SPILLWAY, SPCL DES	EA	1		
441-4020	CONC VALLEY GUTTER, 6 IN	SY	90		
441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	LF	940		
441-6012	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2	LF	80		
500-3201	CLASS B CONCRETE, RETAINING WALL	CY	130		
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	CY	3		
515-2050	HANDRAIL SPECIAL DESIGN	LF	200		
603-2018	STN DUMPED RIP RAP, TP 1, 18 IN	SY	12		
603-7000	PLASTIC FILTER FABRIC	SY	12		
610-0306	REM METAL GATE - STA 100+96 LT	EA	1		
634-1200	RIGHT OF WAY MARKERS	EA	7		
999-0001	SIDEWALK TURN-DOWN WALL (SEE DRWG 5-0002)	LF	43		
999-0002	SIDEWALK TURN-UP WALL (SEE DRWG 5-0003)	LF	260		
999-0003	REMOVE AND RECONSTRUCT EXIST MAILBOXES	EA	4		
	PERMANENT EROSION CONTROL				
700-6910	PERMANENT GRASSING	AC	0.20		
700-7000	AGRICULTURAL LIME	TN	1		
700-8000	FERTILIZER MIXED GRADE	TN	0.20		
700-8100	FERTILIZER NITROGEN CONTENT	LBS	10		
700-9300	SOD	SY	300		
716-2000	EROSION CONTROL MATS, SLOPES	SY	150		
	TEMPORARY EROSION CONTROL				
163-0232	TEMPORARY GRASSING	AC	0.20		
163-0240	MULCH	TN	2		

**EXHIBIT I
 BID SCHEDULE
 ITB 19-403, BRIARWOOB SIDEWALK PROJECT**

163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	1		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	550		
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	2		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	1		
171-0010	TEMPORARY SILT FENCE, TP A	LF	1100		
	SIGNING AND MARKING				
611-5551	RESET SIGN	EA	3		
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	3		
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	4		
636-2070	GALV STEEL POSTS, TP 7	LF	25		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	3		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	1100		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	560		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	28		
653-1804	THERMOPLASTIC SOLID TRAF STRIPING, 8 IN, WHITE	LF	140		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	100		
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	40		
654-1001	RAISED PVMT MARKERS TP 1	EA	14		
654-1003	RAISED PVMT MARKERS TP 3	EA	7		
657-1085	PREFORMED PLASTIC SOLID PVMT MKG, 8IN, CONTRAST (BLACK-WHITE), TP PB	LF	170		
	UTILITY				
670-9730	RELOCATED EXIST WATER METER, INCL BOX	EA	3		
647-6300	LOOP DETECTOR, 6FT X40FT, QUADRUPOLE	EA	2		

TOTAL

**EXHIBIT I
BID SCHEDULE
ITB 19-403, BRIARWOOB SIDEWALK PROJECT**

Total Bid Excludes City Controlled Contingency

Total Base Bid Amount: _____

Total Base Bid Amount in Words: _____

Contractor: _____

Signature: _____

Print: _____

Date: _____

THIS PAGE MUST BE COMPLETED AND SUBMITTED AS A PART OF YOUR BID