



DATE: April 10, 2020

TO: All Bidders

FROM: City of Brookhaven Purchasing Department

RE: ITB No. 20-106, S. Bamby Drainage Improvements Phase III and IV Project

Please see Addendum No. 2 for the above-referenced solicitation.

ADDENDUM NO. 2
ITB 20-106
S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT

A. The following change has been made to the above-referenced solicitation.

Add: General Notes (Due Date)

Delete: Pages 54-57 (Bid Schedule)

Add: Revised Pages 54-57 (Bid Schedule)

Add: Questions and Answers

B. All other terms and conditions remain the same.

ADDENDUM NO. 2
ITB 20-106, S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT
GENERAL NOTES

Due to the current Shelter in Place mandate, the revised protocol for ITB is as follows:

Delivery Method- All bids must be delivered or received by carrier on Tuesday, April 21, 2020, from 9:00 am -2:30 pm at City of Brookhaven, 4362 Peachtree Road Brookhaven, GA 30319.

Public Bid Opening- The bid opening for ITB will be held via conference call on Tuesday, April 21, at 2:30 pm EST. The conference dial-in information is below. The bid tab will be posted on the City's website.

Conference # 404-637-0550
PIN: 1217.

**ADDENDUM NO. 2
EXHIBIT K
REVISED 4/10/2020 PAGE 54
BID SCHEDULE**

ITB 20-106, S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT

Site Preparation and Mobilization		Est. Qty	Unit	Unit Cost	Total Cost
1	Mobilization and Demobilization	1	LS		
2	Maintenance of Traffic / Project Signage	1	LS		
3	Orange Barrier / Tree Protection Fence	575	LF		
4	Construction Staking and Layout	1	LS		
5	Clearing and Grubbing (Including Tree Removal < 12" DBH)	0.78	AC		
6	Tree Cutting and Mulching Including Stump Removal (12" DBH and greater)	10	EA		
Demolition					
7	Asphalt - Saw Cutting and Removal	1900	SF		
8	Concrete - Saw Cutting and Removal (Driveways)	825	SF		
9	Concrete - Saw Cutting and Removal (Sidewalk)	240	SF		
10	Granite Curb Removal (Salvage if possible)	720	LF		
11	18" CMP Removal	135	LF		
12	Storm Structure Removal	3	EA		
13	Cap/Seal Storm Pipe End	4	EA		
14	Demolish Concrete Flume	300	SF		
15	Demolish Modular Block Wall	175	SF		
16	Misc. Pipe Removal (< 12" Dia.)	40	LF		
17	Remove / Replace Woven Wire Fence	165	LF		
Erosion and Sediment Control					
18	Installation & maintenance - Silt Fence Type S, Complete (Sd1-S)	1,200	LF		
19	Temporary Seeding Complete [Ds1]	0.7	AC		
20	Mulch Complete [Ds2]	0.7	AC		
21	Permanent Seeding [Ds3]	0.5	AC		
22	Permanent Sod [Ds4]	0.28	AC		
23	Slope Stabilization (Ss)	330	SY		
24	Storm Inlet Protection (Pig in Blanket)	11	EA		
25	Storm Inlet Protection (Sd2-F)	3	EA		
26	Outlet Protection (St)	5	CY		
27	Drainage Ditch (Di)	115	LF		
28	Select Riprap Placement	5	CY		
29	Construction Entrance (Co)	1	EA		

**ADDENDUM NO. 2
EXHIBIT K
REVISED 4/10/2020 PAGE 55
BID SCHEDULE**

ITB 20-106, S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT

Storm Structures & Piping		EST. Qty	Unit	Unit Cost	Total Cost
30	18" Reinforced Concrete Pipe, Class III	750	LF		
31	24" HDPE Pipe	373	LF		
32	24" Reinforced Concrete Pipe, Class III	25	LF		
33	36" Reinforced Concrete Pipe, Class III	166	LF		
34	GDOT 1125 Headwall (36")	1	EA		
35	48" Dia. Pre-Cast Concrete Manhole (up to 8' Deep)	11	EA		
36	48" Dia. Pre-Cast Concrete Manhole (up to 16' Deep)	2	EA		
37	60" Dia. Pre-Cast Concrete Manhole (up to 8' Deep)	4	EA		
38	Reset Existing Double-Wing Catch Basin Top	1	EA		
39	GDOT 1033 / 1034 Catch Basin Top	11	EA		
40	GDOT 1011A Standard Manhole Top	3	EA		
41	Pedestal Top / Grate Inlet	3	EA		
Water Line Relocation					
42	12" D.I.P. Water Main (Including all appurtenances. See plans)	125	LF		
43	8" D.I.P. Water Main (Including all appurtenances. See plans)	485	LF		
44	6" Plug (including R.J.)	2	EA		
45	6" Solid Sleeve (including R.J.)	2	EA		
46	Connect to Existing Water Lines (all sizes)	6	EA		
47	Service Connections Assembly	19	EA		
Roadway, Driveway & Sidewalk Repair					
48	New Pavement Replacement. Including backfill, compaction and subgrade per City of Brookhaven and GDOT spec. (open cut areas)	210	SY		
49	Pavement Replacement (Mill & Overlay, excluding open cut areas)	390	SY		
50	Reset Granite Curb (Assume 50% Salvaged)	330	LF		
51	Set New Granite Curb	240	LF		
52	Thermoplastic Marking Arrow, Type 2, White	1	EA		
53	Thermoplastic Solid Traffic Stripe, 5 in, Yellow	134	LF		
54	Thermoplastic Skip Traffic Stripe, 5 in., Yellow	42	LF		
55	Thermoplastic Solid Traffic Stripe, 5 in., White	120			
56	Concrete Replacement (Driveways)	825	SF		
57	Concrete Replacement (Sidewalk)	660	SF		
58	Handicap Ramp	2	EA		
59	Replace Signage	1	LS		
				Total Cost	

ADDENDUM NO. 2
EXHIBIT K
REVISED 4/10/2020 PAGE 56-57
BID SCHEDULE
ITB 20-106, S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT

Misc. Site Work (If Required)		Est. Qty	Unit	Unit Cost	Total Cost
60	Relocate Existing Wooden Fencing (if required)	160	LF		
61	Mail Box Relocation	1	EA		
62	Relocate Storage Shed	1	EA		
				Total Cost	

Total Bid

Total Base Bid Amount (Items 1-59): _____

Total Base Bid Amount in Words (Items 1-59): _____

Total Base Bid Amount (Items 60-62): _____

Total Base Bid Amount in Words (Items 60-62): _____

Contractor: _____

Signature: _____

Print: _____

Date: _____

THIS PAGE MUST BE COMPLETED AND SUBMITTED AS A PART OF YOUR BID

ADDENDUM NO. 2

ITB 20-106

S. BAMBY DRAINAGE IMPROVEMENTS PH III & IV PROJECT

A. The following are questions received and City of Brookhaven responses for the above- referenced solicitation:

1. Would you be able to tell me the allowable lane closure hours for this project? I assume it is not the same as the 7-7 work hours.

Please see page 32 of the solicitation.